

1-040909

11-9

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
WICHITA STATE OFFICE BUILDING
WICHITA, KANSAS 67202

API number: 15-151-21,814 - 00-00

W/2 NW NW /4 SEC. 14 , 28 S, 12 W
4620 feet from S section line
4950 feet from E section line

Operator license# 3959

Lease Hillard well # 1

Operator: Siroky Oil Management, Inc.

County Pratt

147.75

Address: P.O. Box 464
Pratt, KS 67124-0464

Well total depth 4546 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe: 8 5/8 inch @ 260 feet

Aband. Oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11:30 a.m. Day: 09 Month: November Year: 1994

Plugging proposal received from: Kevin Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: 5 1/2" at 4545' w/120 sx cement, PBSD 4545', Perfs at 4363-67'

1st plug sand back to 4310' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by: Richard Lacey

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00 p.m. Day: 09 Month: November Year: 1994

Actual plugging report:

1st plug sanded back to 4310' and dumped 5 sx cement on top of sand bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 5 1/2" casing.

INVOICED

I did [X] / did not [] observe the plugging.

Stephen J. Pfeiffer

12-5-94

DATE 4/7/94

RWD 12-05-94