

To: 1041135  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
180 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 151-21,847-00-00  
W/2 SW SE, SEC. 14, T. 28 S, R. 12 W/2  
660 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30128  
Operator: Kenneth S. White  
Name  
Address 200 E. 1st, Ste. 405  
Wichita, KS 67202

Lease Name Rosenbaum Well # 1  
County Pratt  
Well Total Depth 4600 149.50 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gressel Oil Field Services Inc. License Number 3004  
Address P.O. Box 438, Haysville, KS 67060

Company to plug at: Hour: 10:15 a.m. Day: 29 Month: 12 Year: 19 95

Plugging proposal received from Ed Gressel  
(company name) Gressel Oil Field Service Inc. (phone) 316-463-5161

logs: 5 1/2" at 4600' w/200 sx cement, PBSD 3820', Perfs at 4277-82, CIBP at 4120', 4041-46, 4008-12, 3878-84, 3825-29, 3730-34'

1st plug set CIBP at 3700' and dump 2 sx cement on top through bailer, 8 5/8" wiper plug

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 29 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3700' and dumped 2 sx cement on top through  
bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1734' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

**INVOICED**  
DATE JAN 12 1996  
INV. NO. 44562  
12-29 FEB 29 1996

Signed Steve Pfeifer  
(TECHNICIAN)