

1-040912

11-9

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
WICHITA STATE OFFICE BUILDING  
WICHITA, KANSAS 67202

API number: 15-151-21,813-00-00

SE NE NE /4 SEC. 15, 28 S, 12 W  
4290 feet from S section line  
330 feet from E section line

Operator license# 3959

Lease Rosenbaum E well # 2

Operator: Siroky Oil Management, Inc.

County Pratt

148.88

Address: P.O. Box 464  
Pratt, KS 67124-0464

Well total depth 4581 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe: 8 5/8 inch @ 271 feet

Aband. Oil well X, Gas well   , Input well   , SWD   , D & A   

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9:45 a.m. Day: 09 Month: November Year: 1994

Plugging proposal received from: Kevin Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: 5 1/2" at 4576' w/120 sx cement, BP @ 4150', Perfs at 4097-99'

1st plug sand back to 4040' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by: Richard Lacey

Plugging operations attended by agent? All[ X ], Part[    ], None[    ]

Completed: Hour: 10:15 a.m. Day: 09 Month: November Year: 1994

Actual plugging report:

1st plug sanded back to 4040' and dumped 5 sx cement on top of sand bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.

I did     observe the plugging.

Stephen J. Peeples  
(agent)  
RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1994  
Form CP-2/3  
WICHITA, KANSAS

INVOICED  
DATE 12-5-94  
INV. NO. 41790