

6-26 15-151-10434-00-00

To: 1 120444  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- NA  
NE NW SE, SEC. 22, T. 28 S, R. 12 W/E  
2310 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name & Address: P.O. Box 167  
Lyons, KS 67554

Lease Name Chitwood Well # H-4  
County Pratt 145.41  
Well Total Depth 4474 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 2 p.m. Day: 26 Month: 6 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-028-2457

were: 5 1/2" at 4472' cemented with 200 sx, PBD 4100', Perforated at 3700'

1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, release 8 5/8" wiper plug  
and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:45 p.m. Day: 26 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing to 3650' and dumped 5 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 250 lbs. hulls, 10 sx gel, 50 sx cement,  
6 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 960' of 5 1/2" casing

(If additional description is necessary, use BACK of this report)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
I did not observe this plugging.

DATE 7-10-90

Signed Steve Durrant (TECHNICIAN)

INV. NO. 28570

# S C H L U M B E R G E R

## WELL SURVEYING CORPORATION

Location of Well

22-28s-12w

H-4

Elevation: 1864' DF

COMPANY: LION OIL REFG. CO.

WELL: MAWDSLEY # 1

RUN NO.: ONE

FIELD: CHITWOOD

SURVEY: SEC. 22-28s-12w

COUNTY: PRATT

STATE: KANSAS

FILING No. NE-11W-SC

COUNTY:  
FIELD OR  
SURVEY:  
WELL:  
COMPANY:

First Reading	:	4406	ft.
Last Reading	:	3650	ft.
Footage Measured	:	756	ft.
Casing Shoe Depth:	{	310	ft.
	DRILLER	:	
	SCHLUMBERGER	:	* ft.
Bottom Depth	DRILLER	:	4474 ft.
Max. depth reached	:	4406	ft.

### DIAMETER OF HOLE

from Cag. to Btm. 7 7/8"

from \_\_\_\_\_ to \_\_\_\_\_

from \_\_\_\_\_ to \_\_\_\_\_

Bottom Temperature: \_\_\_\_\_ °F

### MUD CHARACTERISTICS

Nature: Zeogel

Weight: 10.0

Viscosity: 36

Resistivity: 0.2 @ 45 °F

### REMARKS

Measurements from rotary bushing.

Spacings:

AM 18"

OA 13'

DATE February 16, 1944 OBSERVERS O. C. Clift