

1 060810

R 257

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,791-000A

NE NE NW, SEC. 13, T 31 S, R 41 W/EX

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Barnhardt Well # 1

Operator: Berexco, Inc.
Name & Address: 970 Fourth Financial Center
Wichita, KS 67202

County Morton 188.83

Well Total Depth 5810 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1568

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 4:00 pm Day: 1 Month: February Year: 19 86

Plugging proposal received from Ken Malone

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3350' Anhydrite 2549'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 750' with 30 sx cement solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to arcuate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:00 pm Day: 1 Month: Febraury Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2549' with 50 sx cement, 2nd plug at 2170' with 50 sx cement, 3rd plug at 1600' with 50 sx cement, 4th plug at 750' with 30 sx cement, 5th & 6th plugs- solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell (if additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 26 1986

INV. NO. 12676

RECEIVED STATE CORPORATION COMMISSION

FEB 24 1986

Signed Paul A. Luthi (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1 - 19 - 86 month day year

API Number 15- 129-20,791-0000

OPERATOR: License # 5363
Name BEREXCO INC
Address 970 Fourth Financial Center
City/State/Zip Wichita, KS 67202
Contact Person Pete Wilson
Phone (405) 848-1165

NE NE NW 13 31 41 East
Sec. Twp. S. Rg. X West
4950 Ft. from South Line of Section
2970 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5147
Name BEREDCO INC.
City/State Wichita, KS

Nearest lease or unit boundary line 330 feet
County MORROW

Lease Name Barnhardt Well # 1
Ground surface elevation 3350 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 X 2

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Depth to bottom of fresh water 225
Depth to bottom of usable water 525
Surface pipe planned to be set +1600'
Projected Total Depth 5700' feet
Formation LOWER MORROW

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon starting production casing.

Date 1-16-86 Signature of Operator or Agent Title Exec Vice-Pres

For KCC Use:
Conductor Pipe Required 450 feet; Minimum Surface Pipe Required 450 feet per 1 2
This Authorization Expires 7-1-7-86 Approved By 1-17-86

Move in 1-18-86

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1550' any feet depth with 50 60/40 pozmix, 6% gel
2nd plug @ 750 30
3rd plug @ 40 10
4th plug @
5th plug @
(2) Rathole with 10 sxs (b) Mousehole with 10 sxs

PUSHER Ken Madene
TD 5810 FORMATION
SURFACE PIPE 1568 @ 8 3/8"
ANHYDRITE 25 49 ELEVATION 3350
STARTING TIME & DATE 2:15 PM
COMPLETION TIME & DATE 2:15 PM
1st PLUG @ 2249 FT. W/ 50 SX
2nd PLUG @ 2170 FT. W/ 50 SX
3rd PLUG @ 1600 FT. W/ 50 SX
4th PLUG @ 750 FT. W/ 30 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Dow Well
TECHNICIAN Gas Tech w/ 50 any w/ 50 60/40 6%

RECEIVED STATE CORPORATION COMMISSION FEB 24 1986 CONSERVATION DIVISION Wichita, Kansas