

To: 1020144
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-10-88
API NUMBER 15-129-20,781-0001
C NW NW, SEC. 24, T 31 S, R 41 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703
Operator: J.M. Huber Corporation
Name & Address: 7120 I-40 West, Suite 232
Amarillo, TX 79106

Lease Name Randall McComb Well # 24-1
County Morton 180.38
Well Total Depth 5550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1584

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J.M. Huber Corporation License Number 5703

Address 7120 I-40 West, Suite 232, Amarillo, TX 79106

Company to plug at: Hour: 10 a.m. Day: 9 Month: 5 Year: 19 88

Plugging proposal received from Jerry Trout

(company name) J.M. Huber Corporation (phone) 806-353-9837

were: 5 1/2" at 5549' PBD 5332' Perfs at 5316-21'

1st plug set CIBP at 5332' and 5240' with 2 sx cement on top.

2nd plug shoot off 5 1/2" at 500', run tubing to 1660' and pump 50 sx cement,

3rd plug pull tubing to 700' and pump 35 sx cement.

4th plug solid bridge plug pushed down 8 5/8" to 40' and fill to top with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 p.m. Day: 10 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5332' and CIBP at 5240' with 2 sx cement on top.

2nd plug shot 5 1/2" off at 500' and ran tubing to 1660', then pumped 50 sx cement,

3rd plug pulled tubing to 700' and pumped 35 sx cement.

4th plug solid bridge plug pushed down 8 5/8" to 40' and filled to top with 10 sx cement.

Remarks: Used Class H cement by Halliburton. Recovered 500' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-19-88

INV. NO. 20774 AUG 3 1988
5-10

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
5-17-88
MAY 17 1988
CONSERVATION DIVISION
Wichita, Kansas