

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

15-025-00033-0000

FILE NO. 43-41

LOCATION C NE-SW

SEC. 4 TWP. 31 RGE. 21W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease F.L. Darley

Operator Great Bend Pipe Supply Co. Address Box 414 Great Bend Kansas

Field _____ County Clark

Total Depth 6567 Feet.

Plugging Contractor Forbes Casing Pulling Co

Plugging Contractor's License No. 49

Address Great Bend Kansas
(Describe Briefly the manner in which the well was plugged)

20" 98' C.W.C. 5 1/2" 5205' cut 125 sq. hole filled
with sand to 5190' Dump 5 cu cement Mud to
380' Spotted 62 cu cement Top of cement 280'
Mud to 20' set rock bridge 20 cu cement top-
35 cu gell mud circulated through 5 1/2" at 1480' and
40 cu " " " " " " 5 1/2" " 625' before shutting

Current lowest fresh water approx 260'

this hole was drilled by
Stross Petroleum Co
and they did not set
the surface pipe follow
the lowest fresh water

M. S. Rivers
District Conservation Agent

Date 9-28-57

STATE COR. COM.

SEP 30 9-30-57

PLUGGING
FILE SEC. 4 T. 31 R. 21W
BOOK PAGE 43 LINE 41