

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-0451-20538-0000

RECEIVED
CORPORATION COMMISSION
DEC - 8 1981
12-8-81
CONSERVATION DIVISION
Wichita, Kansas

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Imperial Oil Co.

Complete Address 720 Fourth Financial Center Wichita Kansas 67202

Lease Name Emel B. Well No. 1-4

Location 60' N + 55' E of W 1/2 of SE NW Sec. 4 Twp. 31 Rge. 21W (East)(West)

County Clay Total Depth 5245'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rob Liger Drilling Co. Rig #6

Address _____ License No. _____

Operation Completed: Hour: 8:30 A.M. Day: 1 Month: December Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 26' of 8 7/8" surface casing cement circulated. The
annular is at 1080'. 1st plug 1000' with hole full of heavy
mud with 50 lbs cement. 2nd plug 600' push rubber
plug down and pump 40 lbs of cement on top of it. 3rd plug
at 40' to 0' on solid bridge with 10 lbs of cement. Then
pumped 5 lbs in rat hole. Plugging accomplished
by seal cementing out of Great Bend Kans.
Cement used was common with 2% Jell + 2% C.C.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthi
Conservation Division Agent