


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 15 Twp. 29 Rge. 7W (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner Sunray Mid-Continent Oil Company
Lease Name Bates Well No. 2
Office Address 321 West Douglas, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed October 24, 1960
Application for plugging filed February 13, 1962
Application for plugging approved February 14, 1962
Plugging commenced March 6, 1962
Plugging completed March 8, 1962
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production November 12, 1961
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Mississippi-Chert Depth to top 4110' Bottom 4150' Total Depth of Well 4525' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi - Chert	Gas	4110'	4150'	8 5/8"	304'	-0-
				5 1/2"	4209'	3400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud from T.D. to 4100' and set 5 sacks cement plug. Filled with mud to 250'. Set 10' rock bridge from 250' to 240'. Filled hole with 3 1/2 yards of ready mix cement from 240' to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1962
3-12-62
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Gary W. Pierce (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce
321 West Douglas, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 62

My commission expires July 13, 1963

W. M. Outgum
Notary Public.

15-095-01778-0090
PR-4

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
October 11, 1960

Contractor: Stickle Drilling Company
Date Commenced: September 26, 1960
Date Completed: October 9, 1960

Bates No. 2
C SW/4 SE/4 NE/4
Sec. 15-29S-7W,
Kingman Co., Kansas

DRILLER'S LOG

DEPTH FIGURES INDICATE BASE OF FORMATION:

Surface clay	30
Sand	70
Shale & shells	306
Red Bed and Shale	1110
Anhydrite	1150
Shale & shells	1275
Shale-Lime	1460
Lime & shale	1655
Shale & lime	2665
Lime & shale	2785
Shale & lime	2960
Lime & shale	3187
Shale & lime	3400
Lime	3479
Lime and shale	3525
Shale & lime	3625
Lime & shale	3680
Lime	3780
Lime & shale	3845
Shale & lime	3880
Shale & lime	4074
Lime & shale	4195
Shale & lime	4370
Lime & shale	4520
Lime & shale	4525 TD

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1962
3-12-62
CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's Bates Well No. 2, Center of Southwest Quarter of Southeast Quarter of Northeast Quarter of Section 15-29S-7W, Kingman County, Kansas.

Fred E. Stickle
Fred E. Stickle

Notary Public

My commission expires June 25, 1963