

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kingman County. Sec. 15 Twp. 29 Rge. 7 (E) (W)

Location as "NE/CNW/SW" or footage from lines _____

Lease Owner Spector Pipe and Supply Inc.

Lease Name Bates Well No. 1

Office Address Box 169, Russell, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 8-29-57 19

Application for plugging filed 1-12-67 19

Application for plugging approved 1-13-67 19

Plugging commenced February 3, 1967 19


Plugging completed February 6, 1967 19

Reason for abandonment of well or producing formation _____

Depleted

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Viola Depth to top 4500' Bottom 4503' Total Depth of Well 4503' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Viola</u>				<u>8 5/8"</u>	<u>325'</u>	<u>none</u>
				<u>5 1/2"</u>	<u>4499'</u>	<u>3327.31'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3350 feet and dumped 5 sacks of cement. Mudded hole to 300 feet. Set Rock Bridge and finished filling hole with ready-mix cement.

RECEIVED
STATE CORPORATION COMMISSION
2-15-67
FEB 15 1967

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Company 457

Address R.F.D. 4, Great Bend, Kansas

STATE OF Kansas COUNTY OF Russell, ss.

Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1967

My commission expires December 1, 1968


Elsie Coady
Elsie Coady
Notary Public.

Company- SUNRAY MID-CONTINENT OIL CO.
Farm- Bates No. 1

SEC. 15 T. 29 R. 7W
SW SW NE

Total Depth. 4503'
Comm. 8-11-57 Comp. 8-29-57
Shot or Treated.
Cont. Dr. Strickle Drlg.
Issued. 12-7-57

County Kingman
KANSAS



CASING:
8 5/8" 325'
5 1/2" 4499'

Elevation. 1593' RB

Production. 106 BOPD, NW

Figures indicate Bottom of Formations.

sand	165
shale & red bed	220
shale & shells	325
red bed, shale & shells	560
shale & shells	1125
lime	1280
lime & shale	1905
shale & lime	2080
lime & shale	2320
shale & lime	2670
lime & shale	2820
lime	2900
lime & shale	3220
sandy shale	3331
lime	3415
lime & shale	3485
lime	3786
lime & shale	3840
shale & shells	3915
lime & shale	3960
shale & lime	4015
shale & shells	4100
shale & lime	4119
lime	4143
lime, chat & shale	4159
lime	4387
lime & shale	4470
lime	4503
Total Depth	

TOPS:

Lansing	3338
Mississippi Lime	4118
Kinderhook Shale	4392
Viola Ls.	4500

RECEIVED
STATE CORPORATION COMMISSION
2-15-67
FEB 15 1967
CONSERVATION DIVISION
Wichita, Kansas