


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 17 Twp. 29S Rge. 7 (W)  
Location as "NE/CNW/SW" or footage from lines SE 1/4 SE 1/4 NW 1/4  
Lease Owner Drilling and Exploration Company, Inc.  
Lease Name Campbell Well No. 1  
Office Address 811 Union Center Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 19, 1960  
Application for plugging filed June 19, 1960  
Application for plugging approved June 19, 1960  
Plugging commenced June 19, 1960  
Plugging completed June 19, 1960  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4575 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sands		Surface	259'	8-5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Filled hole with mud to 240', placed 20 sax plug from 240' to 196' with pump truck. Filled with mud to 35', placed 10 sax plug from 35' to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
6-30-60  
JUN 30 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Mack Oil Co.  
Address Duncan, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Karl A. Peterson (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl A. Peterson  
811 Union Center Bldg., Wichita, Kansas  
(Address)



SUBSCRIBED AND SWORN TO before me this 28th day of June, 1960  
Elizabeth K. Sutton  
Notary Public.

Re

DRILLING AND EXPLORATION COMPANY, INC.  
Dallas, Texas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1960  
CONSERVATION DIVISION  
WICHITA, KANSAS

DRILLERS WELL LOG

#1 Campbell  
Commenced R.D.: 6-2-60  
Completed R.D.: 6-18-60  
Total Depth: 4575'  
Casing Record: 252' 8-5/8" OD surface casing at 259'.  
SE SE NW Sec. 17-29S-7W  
Kingman County, Kansas  
Elevation: 1593 K.B.  
Initial Production: D&A  
Contractor: Mack Oil Co.

STRATA	DEPTH
Sand & Clay	0' - 167'
Shale	167' - 1105'
Anhydrite	1105' - 1170'
Lime	1170' - 2028'
Shale & Shells	2028' - 2565'
Lime & Shale	2565' - 2760'
Lime	2760' - 2991'
Lime & Shale	2991' - 3339'
Lime	3339' - 4161'
Lime & Chert	4161' - 4251'
Lime	4251' - 4360'
Lime & Chert	4360' - 4393'
Lime & Shale	4393' - 4516'
Lime	4516' - 4530'
Sand	4530' - 4550'
Sand & Lime	4550' - 4575'

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Harold L. Steincamp  
Harold L. Steincamp

Signed and sworn to in my presence this 27th day of June, 1960, by Harold L. Steincamp, a representative of Mack Oil Company.

Elizabeth K. Sutton  
Elizabeth K. Sutton  
Notary Public

My Commission Expires: May 6, 1961