

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Kingman County, Sec. 17 Twp. 29 Rge. 7 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner McCoy Petroleum Co.

Lease Name Castle Well No. # 2

Office Address 502 Union Center ; Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed July 19 71

Application for plugging approved July 19 71


Plugging commenced July 19 19 71

Plugging completed July 23 19 71

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Russell Biberstein

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	218	None
				5 1/2"	4249	3203

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

July 19, 1971 Plugged off bottom. Dumped sand to 3650'. Mixed and dumped 5 sx of cement.

July 23, 1971 Plugged off top. Set 10' rock bridge at 210'. Filled 8 5/8" surface casing with 3000 lb. P.S.I. ready-mix concrete, from 210' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1971
CONSERVATION DIVISION
Wichita, Kansas

8-11-71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.

Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

John Roger McCoy (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) John Roger McCoy

502 Union Center (Address)

Subscribed and sworn to before me this 10th day of August, 1971

Diane E. Charter Notary Public.

My commission expires October 23, 1973



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

CASTLE #2
C. NW. SE SECTION 17-29S-7W
KINGMAN COUNTY, KANSAS

COMMENCED: MAY 28, 1968
COMPLETED: JUNE 7, 1968

OPERATOR - BARBARA OIL COMPANY

DEPTH	FORMATION	REMARKS
FROM To		
0 50	SAND CLAY AND RED BED	RAN 6 JOINTS 3-5/8" CASING, SET @ 225' w/200 SACKS CEMENT.
225 650	SHALE AND RED BED	
650 1140	SHALE	
1140 1360	ANHYDRITE AND LIME	
1360 1620	SHALE AND LIME	
1620 1790	LIME	
1790 2800	LIME AND SHALE	
2800 2950	LIME	
2950 3390	LIME AND SHALE	
3390 3842	LIME	
3842 4190	LIME AND SHALE	
4190 4250	LIME	
4250 TO		RAN 132 JOINTS 5 1/2" CASING, SET @ 4249' w/150 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 - 1971 7-1-71
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C. NW. SE SECTION 17-29S-7W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 11TH DAY OF JUNE, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1972.

