


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Kingman County. Sec. 16 Twp. 29S Rge. 7W ~~EX~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
150' SE of C- SE NW
Lease Owner Zorger Oil Co.
Lease Name Weniger Well No. 1
Office Address 1010 Douglas Bldg., 104 S. Broadway,
Character of Well (Completed as Oil, Gas or Dry Hole) Wichita,
Dry Hole KS 67202
Date Well completed September 4, 1978
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced September 4, 1978
Plugging completed September 4, 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4,193
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	235'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy rotary mud from 4,193 ft. (rotary total depth) to
240 ft. Set plug at 240 ft. and cemented with 40 sacks cement. Filled
hole with heavy rotary mud from 240 ft. to 40 ft. Set solid plug at 40 ft.
and cemented to cellar with 12 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing
pump truck through 4½ inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent of owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

200 N. Main, Wichita, KS 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 1978

My commission expires July 25, 1982

Elsie Willison
Elsie Willison Notary Public.
STATE CORPORATION COMMISSION

SEP 12 1978
9-12-78
CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Zorger Oil Co.

SEC. 16 T. 29S R. 7W
LOC. 150' SE of C-SE NW

FARM Weniger

NO. 1

COUNTY Kingman

ROTARY TOTAL DEPTH 4,193'

COMM. August 25, 1978

COMP. September 4, 1978

CONTRACTOR H-30, Inc.

ISSUED September 11, 1978

CASING

10 3/4"

8 5/8" Set at 235' cemented w/175 sxs cement

ELEVATION 1,605 K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	80'
Red Bed	850'
Shale	1,100'
Shale and Lime	1,800'
Lime and Shale	2,530'
Shale and Lime	2,750'
Lime and Shale	3,140'
Shale and Lime	3,425'
Lime	4,193'
Rotary Total Depth	4,193'

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas

County of Sedgewick

ss:

Subscribed and Sworn to before me a Notary Public

in and for said county and state this 11th day of
September, 1978.



My Commission Expires:

July 25, 1982

Elsie Willison
Elsie Willison - Notary Public
RECEIVED
STATE CORPORATION COMMISSION
9-12-78
SEP 12 1978

CONSERVATION DIVISION
Wichita, Kansas