

15-095-00520-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Brand A

WELL NUMBER A #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 16 TWP. 29 RGE. 7W (E) or (W)

COUNTY Kingman

Date Well Completed 1953

Plugging Commenced 6/25/86

Plugging Completed 6/27/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil & Gas Corporation

ADDRESS 3545 NW 58th Street/Oklahoma City, Okla. 73112

PHONE#(316, 672-9388) OPERATORS LICENSE NO. 5447

Character of Well Oil & Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Lansing Depth to Top 3727 Bottom 3773 T.D. Original 4515 Plug back 3830

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	278'	0
				5 1/2"	4512'	2820

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded back to 3675 & dumped 5 sacks of cement on top of sand
Shot off & recovered 2820 of 5 1/2". Pumped 3 sacks of hulls, 15 sacks of gel & 70
sacks of 60/40 pozmix cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HAYES WELL SERVICE License No. KCC #5429

Address Box 108 Attica, Kansas 67009

STATE OF Kansas COUNTY OF Harper, ss.


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Hayes Well Service [Signature]

(Address) Box 108 Attica, Ks. 67009

SUBSCRIBED AND SWORN TO before me this 25th day of July, 19 86

Rogena Grigsby
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KANSAS
Notary Public



Form CP-4
Revised 08-84

JUL 23 1986
7-23-86