

15-095-00521-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 20 Twp. 29 Rge. 7 (E) W (W)

Location as "NE/CNW\*SW\*" or footage from lines NW NW NW  
Lease Owner George B. Siegrist  
Lease Name Walters #1 Well No.  
Office Address Hutchinson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6-12-58 19  
Plugging completed 6-14-58 19  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hamplek  
Producing formation Depth to top Bottom Total Depth of Well 4562 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	310'	none
				5-1/2"	4210'	3343'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole and found it open. Filled w/sand to 200' and ran 5 sacks of cement. Pulled casing to 1600' and circulated with 30 sacks of gel mud. Pulled pipe to 310' and pumped in 25 sacks of cement. Pulled rest of casing, cleared hole and mudded to 40', set a 10' rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
6-19-58  
JUN 19 1958

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor West Supply Co., Inc. (If additional description is necessary, use BACK of this sheet)  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George B. Siegrist  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 58

My commission expires 9-27-58 Thomas V. Duggin Notary Public.

PLUGGING  
FILE SEC 20 T 29 R 7W  
BOOK PAGE 106 LINE 29

15-095-00321-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- GEORGE B. SIEGRIST  
Farm- Walters No. 1

SEC. 20 T. 29 R. 7W  
NW NW NW

Total Depth. 4562'  
Comm. 12-6-57 Comp. 12-23-57  
Shot or Treated.  
Contractor. Red Drlg.  
Issued. 5-3-58

County. Kingman  
KANSAS



Elevation. 1561'

Production. 3,000,000 CFG

Figures indicate Bottom of Formations.

cement	300
red bed	716
shale & shells	1285
lime & shale	1630
lime & shale strks	1745
shale & lime	1890
lime & shale	2065
shale & lime	2408
lime & shale	2555
shale & lime strks	2710
lime	2750
lime & shale	3265
sandy shale	3355
lime	3898
lime & shale	3974
shale & lime	4115
lime	4130
lime & chert	4207
lime	4351
lime & shale	4374
lime	4383
shale	4499
sand & shale	4505
sand	4542
sand	4562
Total Depth	

TOPS:	
Doulgas	3247
Lansing Lime	3355
Kansas City (scout)	3635
Mississippi Lime	4110
Simpson Sand	4505

RECEIVED  
STATE CORPORATION COMMISSION

JUN 11 1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 20 T. 29 R. 7W  
BOOK PAGE 106 LINE 29