


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kingman County. Sec. 20 Twp. 29S Rge. 7 W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW NW SW

Lease Owner Shaffer & Se Ro Bee Oil
Lease Name Matlack Well No. 1
Office Address 404 Wolcott Bldg, Hutchinson, Ks. 67501
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed August 13, 1976
Application for plugging filed August 13, 1976
Application for plugging approved August 13, 1976
Plugging commenced August 13, 1976
Plugging completed August 13, 1976
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4155'
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 250 feet. Pumped 35 sacks cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 15 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 5 sacks of cement.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK
John C. Graves

(employee or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
910 Union Center, Wichita, Kansas 67202
(Address)

Subscribed and Sworn to before me this 19th day of August 1976

My commission expires February 2, 1980

[Signature]
Courtney M. Graves
Notary Public.



ROTARY DRILLERS' LOG

OPERATOR: SHAFER & SEROBEE OIL DRILLING COMMENCED: August 6, 1976
 404 Wolcott Building
 Hutchinson, Kansas 67501

CONTRACTOR: GRAVES Drilling Co., Inc. DRILLING COMPLETED: August 13, 1976
 910 Union Center
 Wichita, Kansas 67202

CASING RECORD: 5 Jts. 204' of used 8-5/8" LOCATION: Matlack No. 1
 cemented with 175 sacks SW NW SW
 Section 20-29S-7W
 Kingman County, Kansas

0 - 204 Red Bed
 204 - 1100 Shale & sand
 1100 - 1510 Shale
 1510 - 2060 Shale & shells
 2060 - 2360 Shale
 2360 - 2980 Shale & lime
 2980 - 3230 Shale
 3230 - 3480 Shale & lime
 3480 - 3830 Lime & shale
 3830 - 4155 Lime
 4155 Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 20 1976
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Phil Graves

STATE OF KANSAS)
) SS:
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 18th day of August, 1976

My commission expires: 2 February 1980



Courtney M. Graves
 Courtney M. Graves Notary Public

copies sent to Kan Encl Co
 summary
 copy comm