

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 207
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-095-21816-00-00
LEASE NAME Mayer
WELL NUMBER 2
990 ft. from S Section Line
2310 ft. from E Section Line
SEC. 20 TWP. 29 RGE. 7 (E) or (W)
COUNTY Kingman

RECEIVED
AUG 04 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

LEASE OPERATOR MTM Petroleum 8-4-03
ADDRESS Box 782, Spivey, KS 67124
PHONE # (620) 532-3794 OPERATORS LICENSE NO. 6236
Character of well oil

Date Well Completed 7-22-02
Plugging Commenced 7/9/03
Plugging Completed 7/11/03

(Oil, Gas, D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 7/9/03 (date)
by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Miss. Depth to Top 4125' Bottom T.D. 4543
Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	233	none
				4 1/2	4234	3440

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Sand at 4062, bail 4 sacks cement. Rip pipe to 3617, 3440, work free. Pull to 1200, pump 35 sacks cement. Pull to 700, pump 35 sacks cement. Pull to 280, circulate cement to surface with 126 sacks. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MTM Petroleum

STATE OF Kansas COUNTY OF Kingman, ss.

Marvin A. Miller, Pres. MTM Petroleum (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Marvin A. Miller Pres.
(Address) P.O. Box 82 Spivey KS 67142

SUBSCRIBED AND SWORN TO before me 31st day of July, 2003

Kathy Hill Notary Public

My commission Expires: 01-04-07

Form CP-4
Revised 05-88

