

STATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-095-19012-0000
API NUMBER C-6123 56,603-C

LEASE NAME Pierce

WELL NUMBER # 1 SWD

660 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 22 TWP. 29 RGE. 7 (E) or (W)

COUNTY Kingman

Date Well Completed 01-07-58

Plugging Commenced 10-04-2000

Plugging Completed 10-04-2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR MESSENGER PETROLEUM, INC.

ADDRESS 525 S. Main Kingman, KS. 67068

PHONE#(316) 532-5400 OPERATORS LICENSE NO. 4706

Character of Well TA

Oil, Gas, D&A, (SWD) Input, Water Supply Well

The plugging proposal was approved on 09-22-2000 (date)

by Mr. Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Chase Group Depth to Top 1480 Bottom 1058 T.D. 2102

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chase Group 1480-1958	SWD	1480	surf.	8 5/8	1480	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set by wire line a 8 5/8 bridge plug @ 1390', spot 10 sx of 60/40 4% gel cement on top of plug, spot 35 sx of 60/40 4% gel cement @ 1075', spot 35 sx of 60/40 4% gel cement @ 675', circulate cement from 250' to surface w/ 65 sx 60/40 4% gel, pull tbg & top off w/ 5 sx 60/40 4% gel. (plugged 10-04-2000 02:30pm.)

Name of Plugging Contractor Jimenez Well Service License No. 3848

Address P.O. Box 257 Attica, KS. 67009-0257

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MESSENGER PETROLEUM, INC.


STATE OF Kansas COUNTY OF Kingman, ss.

Jon F. Messenger (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jon F. Messenger

(Address) 525 S. Main Kingman, KS 67068



Subscribed and sworn to before me this 6th day of October 192000
John M. Wood Notary Public
STATE CORPORATION COMMISSION

My Commission Expires: 9-9-2002

OCT 10 2000
10-10-00
FORM 15-1
CONSERVATION DIVISION
Wichita, Kansas