


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas



Kingman County, Sec. 24 Twp. 29 Rge. 7 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SESE  
Lease Owner Pickrell Drilling Co.  
Lease Name Cox "B" Well No. 1  
Office Address 705 Fourth Natl. Bank Bldg. Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed April 23, 1960  
Application for plugging filed Jan. 25, 1968  
Application for plugging approved Jan. 29, 1968  
Plugging commenced Jan. 26, 1968  
Plugging completed Jan. 30, 1968  
Reason for abandonment of well or producing formation Too much water

If a producing well is abandoned, date of last production 19 62.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Miss Miss. Depth to top 4086 Bottom 4114 Total Depth of Well 4507 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	280'	None
				5 1/2	4503'	3432'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Cemented perforations with 40 sx. of cement from 4505' to 4068'. Pressured up on casing and pressure held at 1,500 lbs. Pulled casing. Mudded hole to 300'. Set 10' rock bridge from 300' to 290'. Mixed and dumped 25 sx. of cement from 290' to 215'. Mudded hole from 215' to 40'. Set 10' rock from 40' to 30'. Mixed and dumped 10 sx. of cement from 30' to base of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 5 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
2-5-68


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.  
Address P.O. Box 1082 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth Natl. Bank Bldg. Wichita, Ks 67202  
(Address)

Subscribed and sworn to before me this 2nd day of February, 19 68



L. M. Whiting  
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 2-25-60

COX "B" 1

Rotary Drilling Completed 3-14-60

LOCATION: SW SE SE, Sec. 24-29S-7W  
Kingman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: 280' (7 jts. Armco spiral weld csg. Set at 278'. Cemented with 170 sacks of cement. Cement circulated. Completed at 4:30 A.M., 2-27-60.

Ran 147 jts., 5 1/2" csg. set at 4507', cemented with 110 sacks of cement. Completed 12:00 A.M. 3-13-60.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Circ. for Samples:

60	Sand	3691'
190	Red Rock	3718'
630	Shale and Clay	3760'
1155	Salt, Shale, Gyp, Anhydrite	4093'
1350	Lime & Shale	4120'
3245	Shale, Lime, Sandly	4135'
3320	Lime & Shale	4150'
3490	Lime	4165'
3827	Lime & Shale	4455'
4110	Lime, Shale, Chert	4460'
(4085)	Mississippi	4465'
4400	Mississippi and 'Kind'	4470'
4444	Kinderhook	4475'
4470	Shale & Lime	4479'
4479	Shale	4483'
4498	Shale & Dolomite	4500'
4505	Simpson Sand	4505'
4505	Rotary Total Depth	

Slope Test:

2000'	00
3000'	00
4000'	00

S.M.L.

2000'	OK
3000'	OK
4000'	OK

**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts ~~Attorney-in-Fact~~ for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
~~Attorney-in-Fact~~  
C. W. Sebitts, Partner

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 17th day of March, 19 60, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 13, 1961

[Signature]  
Notary Public  
Ruth M. Sullivan

*File Copy*