


15-095-01217-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

KINGMAN County. Sec. 24 Twp. 29S Rge. 7W (X) W (W)

Location as "NE/CNW/SW" or footage from lines NW, NW, NW
Lease Owner ROCK ISLAND OIL & REFINING COMPANY
Lease Name HENSON Well No. 1
Office Address 321 DOUGLAS, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY ROTARY
Date well completed SEPT. 4, 19 60
Application for plugging filed SEPT. 4, 19 60
Application for plugging approved SEPT. 4, 19 60
Plugging commenced SEPT. 4, 19 60
Plugging completed SEPT. 4, 19 60
Reason for abandonment of well or producing formation No productible zone.



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Depth to top Bottom Total Depth of Well 4155 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 250' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gunned pits forming heavy mud, filled hole up to 240' with heavy mud, pushed wooden plug to 240' with 1/4 sx. hulls and capped with 15 sx. cement through drill pipe.
Filled hole up to 30', pushed wooden plug with 1/4 sx. hulls to 30' and filled hole up to base of well cellar with 10 sx. cement.
Filled rat-hole with 3 sax. cement.

RECEIVED
CORPORATION COMMISSION
OCT 7 7 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
VERNE A. MORRIS (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris.
ROUTE #2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 60

My commission expires November 12, 1962 Notary Public.



WELL LOG

COMPANY **ROCK ISLAND OIL & REFINING COMPANY, INC.**

SEC. **24 T-29S R. 7W**

FARM **HENSON**

NO. **1**

LOC. **NW, NW, NW**

TOTAL DEPTH **4155'**


COUNTY **KINGMAN CO., KANSAS**

COMM. **August 23, 1960**

COMP. **September 4, 1960**

CONTRACTOR **GARVEY DRILLING COMPANY**

CASING **8 5/8" @ 250' w/200 sax.**



ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|------|---------------------|
| 80 | Surface clay & sand |
| 251 | Red bed |
| 1053 | Shale |
| 1515 | Lime & shale |
| 1675 | Lime |
| 3190 | Shale & lime |
| 3303 | Shale |
| 3455 | Lime & shale |
| 3930 | Lime |
| 4067 | Lime & shale |
| 4103 | Shale & lime |
| 4155 | Mississippi lime |
| 4155 | T. D. |

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 7 1960
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS
 County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 HENSON well.

Verne A. Morris

Subscribed and sworn to before me this 20th day of September 1960

My Commission Expires: November 12, 1962

Garvey
 NOTARY PUBLIC