

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Osborn

WELL NUMBER 1

SPOT LOCATION C/W2 SENE

SEC. 24 TWP. 29 RGE. 7 (X) or (W)

COUNTY Kingman

Date Well Completed NA

Plugging Commenced 7/5/84

Plugging Completed 7/20/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company

ADDRESS Suite 205 Litwin Building, Wichita, Kansas 67202

PHONE # () OPERATORS LICENSE NO. 5123

Character of Well gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? _____

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4260

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	224	none
				4 1/2	4260	3100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
sand from 4203 to 4070 4 sacks cement with Dump Bailer
from 4070 to 4030 Allied pump in 3 sacks hulls 6 sacks jell 115 sacks ceme
60-40 POZ 2% jell 3% ce

Aumeller-Van Goezon on location
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105
Address Box 187, Medicine Lodge, Kansas 67104

STATE OF Kansas COUNTY OF Barber, ss.

(employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, state and matters herein contained and the log of the above-described well and matters herein contained that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
7-30-84
JUL 30 1984

(Signature) [Signature]

(Address) _____



CONSERVATION DIVISION
SUBSCRIBED AND SWORN TO before me this 26th day of July, 1984

Neita Jo Boor
Notary Public

My Commission expires: _____

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 24 T. 29 R. 7 W

MAR 08 1984

API No. 15 — N/A —
County Number

Loc. C W/2 SE NE

County Kingman

Operator CONSERVATION DIVISION
Wichita, Kansas

Pickrell Drilling Company

640 Acres
N

Address
205 Litwin Building, 110 North Market, Wichita, KS 67202


Well No. 1 Lease Name Osborn

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Geologist
Pickrell Drilling Company Donald J. Malone

Spud Date 5-1-62 Date Completed 5-21-62 Total Depth 4262 P.B.T.D. 4221 (Logger)

Directional Deviation Oil and/or Gas Purchaser



Locate well correctly

Elev.: Gr.

DF KB 1547'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (In O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		224'	Common	175	2% gel 3% cc
Production	7 7/8"	4 1/2"	9.5#	4260'	Common	100	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3	3/8" jet	4143'-4148'
TUBING RECORD			3	3/8" jet	4137'-4139'
Size	Setting depth	Packer set at	3	3/8" jet	4121'-4131'
2 3/8" OD	4131'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Treated dwn annulus w/125 gal mud acid - 7500# sand 20/40 in	
7500 gallons gelled wtr. Ave press treating 1750#.	4121'-4148'

INITIAL PRODUCTION

Date of first production 3-12-63	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
Disposition of gas (vented, used on lease or sold) Sold - Basil Gas System (Anadarko Production Purchaser)	Producing interval(s) 4121'-4148'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

15-095-00718-0000

Operator Pickrell Drilling Company DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas

Well No. 1 Lease Name Osborn

S 24 T 29 R 7 W


WELL LOG

Show all important zones of porosity and contents thereof, cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1, 4124'-4137' Gas 4" op 1 hr 5" gauge 802 MCF, 10" 802 MCF, 20" 734 MCF, 60" 734 MCF, Rec. 40' GCM 1576#-1386#, 171#-125#.			Sample Tops: Heebner Lansing Mississippian	3050(-1503) 3296(-1749) 4119(-2572)
DST #2, 4137'-4188' gas to surf 6" gauge 5" 175 MCF, 10-60" 139 MCF. Tool op 1 hr Rec. 90' SO&GCM, BHP 1600#/20", 1584#/30" FP 39/62#.				
DST #3, 4188'-4218' op 1 hr, Rec. 120' GCM, SOC, BHP 420#/20", 358#/20", FP 46/78#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	C. W. Sebitts - Partner
	July 15, 1981

15-095-00718-0000
NOTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita 2, Kansas

LOCATION: Osborn # 1 - C W/2 SE/4 NE/4
 Sec. 24-29S-7W, Kingman County
 Kansas

Rotary Drilling Commenced 5-1-62
 Rotary Drilling Completed 5-12-62

CONTRACTOR: **PICKRELL DRILLING COMPANY.**
 Wichita, Kansas

CASING RECORD: 224' (8 jts.,) 8 5/8" Surface Casing Set with 175 sacks cement. Circulated
 Run 132 jts. casing set @ 4261 with 100 sacks cement. Completed at
 2:15 A. M. 5-12-62

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

	<u>Circulating for Samples</u>	
70' Sand	3742'	4198'
100' Clay & Red Rock	4132'	4208'
224' Red Rock	4137'	4218'
700' Red Rock, Blue shale, Clays, & Gyp.	4165'	4246'
880' Salt, Shale & Shells	4188'	4262'
1570' Lime & Shale		
1760' Lime		
3178' Lime & Shale		
3345' Lime, Shale & Sand	<u>Slope Test</u>	
3807' Lime	1500' 0°	
4122' Lime & Shale	2500' 0°	
4262' Mississippi R.T.D.	3500' 0°	
	4000' 0°	

S. L. M.

3178'
 3416'
 4188'

RECEIVED
 STATE CORPORATION COMMISSION

MAR 08 1964

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By *C. W. Sebitts*
 C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 24th day of May, 19 62, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, Partner, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
 Maxine Johnson

Maxine Johnson
 Notary Public

OSBORN NO. 1

W/2 SE NE Sec 24-29S-7W

Kingman City, KS.

224 Base 8 5/8" w/175 Sx

3815 ESTIMATED T.O.C.

4121-4131

4137-4139

4143-4148

Miss Perfs

4203 PSTD

4260 Base 4 1/2" 9.5# J-SS w/100 Sx Cmt.

4260 LTD

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1984

CONSERVATION DIVISION
Wichita, Kansas

46 0700

10 X 10 TO THE INCH # 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.