

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 25 Twp. 29S Rge. (E) 7 (W)

NORTH

Section Plat grid with 4 columns and 4 rows.

Locate well correctly on above  
Section Plat

Location as "NE/CNW/SE" or footage from lines SE SE SE  
Lease Owner Pickrell Drilling Company  
Lease Name Millard Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 4, 19 62  
Application for plugging filed June 4, 19 62  
Application for plugging approved June 4, 19 62  
Plugging commenced June 4, 19 62  
Plugging completed June 4, 19 62  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was cement obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation Depth to top Bottom Total Depth of Well 4225 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: SIZE 8 5/8", PUT IN 229', PULLED OUT None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 200'. Set Plug.  
Cemented with 20 sacks cement.  
Heavy mud to 35'. Set Plug.  
Cemented with 10 sacks cement  
to bottom of cellar. Plugged  
rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1962  
6-14-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. Sebitts

(If a lawyer or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg., Wichita 2, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of June, 19 62

My commission expires September 24, 1962

Maxine Johnson  
Notary Public.



15-095-01216-0000

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita 2, Kansas  
LOCATION: Millard # 1 - SE SE SE  
Sec. 25-29S-7W, Kingman  
County, Kansas

Rotary Drilling Commenced 5-24-62

Rotary Drilling Completed 6-4-62

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: 229' ( 8 jts. ) 8 5/8" Surface casing cemented with 165 sacks cement.  
Circulated. Completed at 8:30 A. M. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

55'	Sand	<u>CIRCULATED FOR SAMPLES</u>
130'	Red Rock	4106'
230'	Red Rock, & Shale	4116'
750'	Red Rock, Shales, Clay & Anhydrite	4120'
835'	Salt, Shale & Shells	4130'
1280'	Shale, Shells & Lime	4135'
1510'	Lime & Shale	4156'
1675'	Lime	4175'
3350'	Lime & Shale	4225'
3608'	Lime	
4100'	Lime & Shale	<u>Slope Test</u>
4225'	Mississippi R. T. D.	1500' 0°
		2500' 0°
		3500' 0°
		4000' 0°
		<u>S. L. M.</u>
		3255'
		3510'
		3923'

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 14 1962  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.

On this 12th day of June, 1962, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed; and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson  
Maxine Johnson Notary Public