


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Seward County: Sec. 22 Twp. 32 Rge. 34 ~~(E)~~ (W)
Location as "NE/CNW/SW" or footage from lines 330' N, 330' W of Center
Lease Owner Cities Service Oil Company
Lease Name Hitch "G" Well No. 2
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-15 1957
Application for plugging filed 7-15 1957
Application for plugging approved 7-19 1957
Plugging commenced 7-20 1957
Plugging completed 7-22 1957
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Phillippe
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 424.2 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Anhydrite</u>	<u>Anhydrite</u>	<u>1641</u>	<u>1683</u>	<u>8-5/8" 24#</u>	<u>1667</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 50 sacks cement at 4220', 50 sacks cement at 2750', 50 sacks cement at 2450', 50 sacks at 1660', heavy rotary mud was put in to 20' of ground level, at which point the casing was filled with cement to 4' of surface and the casing was cut off and a steel cap welded on.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Co.
Address Duncan, Oklahoma

STATE OF KANSAS COUNTY OF SEWARD, ss.
W. J. Devaney (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Devaney
Box 70, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of July, 19 57

My commission expires 5-23-1961

J. T. Mabrey J. T. Mabrey
Notary Public.

PLUGGING
FILE SEC 22 T. 32 R. 34 W
BOOK PAGE 28 LINE 8