

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20777-0001

LEASE NAME Hitch N

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

330 FSL Ft. from S Section Line

330 FEL Ft. from E Section Line

SEC. 26 TWP. 32S RGE. 34W(X) or (W)

COUNTY Seward

Date Well Completed 10/31/84

Plugging Commenced 8/12/95

Plugging Completed 8/27/95

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Morrow Depth to Top 5706/5713 Bottom 5719 T.D. 6430

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Morrow</u>	<u>Gas</u>	<u>5706</u>	<u>5719</u>	<u>8 5/8"</u>	<u>1686</u>	
				<u>5 1/2"</u>	<u>5929</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

POOH w/ 176jts 2 3/8 tbq. Set CLBP @ 5650'. Dump bailer and spot 2sks cmt on BP. Weld on pull sub & took stretch measurement. HLS cut csg off @ 1730'. TOOH w/ 40 jts of csg. TIH w/tbg and set plugs as follows: 50sks @ 1716', 40sks @ 656', 10sks @ 40'. Cut csg off 4' below GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Co. License No. 05866

Address 713 S. Simpson, Ulysses, KS 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

Subscribed and sworn to before me this 7th day of November, 1995

[Signature]
Notary Public

7-14-99



RECEIVED
KANSAS CORPORATION COMMISSION
NOV 09 1995
CONSERVATION DIVISION
WICHITA, KS
My Commission Expires: