

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20587-0000

LEASE NAME Hitch J

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

4280 Ft. from S Section Line

4980 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 31 TWP. 32S RGE. 34 (X) or (W)

ADDRESS P. O. Box 26100

COUNTY Seward

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 4/15/82

Character of Well Oil

Plugging Commenced 12/15/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/17/94

The plugging proposal was approved on 9/15/94 (date)

by Glen Barlow (KCC District Agent's name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Chester Depth to Top 6101 Bottom 6119 T.D. 6360

Show depth and thickness of all water, oil and gas formations.
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Chester</u>	<u>Oil</u>	<u>6101</u>	<u>6109</u>	<u>8 5/8"</u>	<u>1715</u>	
				<u>5 1/2"</u>	<u>6355</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

PU 96jts of 2 3/8" tbq & 5 1/2" cmt retainer. Set retainer @ 2968. Pumped 100sks 60/40 Class C Pozmix, displaced slurry to retainer. TOOH w/ tbq & RU HLS & cut csq w/jet cutter @ 1824. RD wireline & work csq. Csq came free, LD 43jts & cutoff of 5 1/2" csq. RIH w 59jts 2 3/8" tbq & spotted 70sks plug of 60/40 Class C Pozmix w/6%gel & 2% Cacl2 @ 1835. (See back of form)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Well Service Co. License No. 5866

Address Box 466, Ulysses, Ks 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Ledlow

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 26th day of December, 19 94

Sammy L Padilla
Notary Public

My Commission Expires: 8-21-96

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1994
REGISTRATION DIVISION
WICHITA, KANSAS

Lay down 37jts & spot 12sks plug @ 30'. RD cementers & ND wellhead. Did out cellar & cut 8.5/8" surface csg off 4' below GL. Weld on plate.