

15-175-20477-0000

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1980

FORM CP-4

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 31 Twp. 32S Rge. 34 ~~W~~
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines
C-SW-SW-SW.

Lease Owner Mohawk Energy Corporation
Lease Name HITCH Well No. #2-31

Office Address 2401 4th Natl. Bk. Bldg, Tulsa, OK 74119
Character of Well (Completed as Oil, Gas or Dry Hole)

DRY HOLE

Date Well completed September 8, 1980

Application for plugging filed September 10, 1980

Application for plugging approved 19

Plugging commenced September 10, 1980

Plugging completed September 10, 1980

Reason for abandonment of well or producing formation

DRY HOLE


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.

Producing formation - Depth to top - Bottom - Total Depth of Well 6243'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	3-5/8"	0'	1715'	8-5/8"	1715'	NONE
	Case			Surface		
	Casing			Casing		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged well with 60 sk. plug @1750' - 1650'; 30 sk. plug @800' - 750';
10 sk. plug @40' - 0'. 5 sk. plug in Rathole. Job complete at 7:30 PM
September 10, 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF Kansas COUNTY OF Seward, ss.
R.J. Patrick (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

NRG Drilling, Inc, Box 1157, Liberal, KS 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 1980

Notary Public.

My commission expires

STATE OF KANSAS NOTARY PUBLIC	A. J. PARNELL Seward County, Kansas My Appt. Exp. 7-7-81
----------------------------------	--

- Orig.: State ✓
2 - Mohawk Exploration
2 - File
1 - Plugger, C. Thomas, Jr.

DRILLER'S LOG

MOHAWK ENERGY CORPORATION

HITCH #2-31
C-SW-SW-SW Sec. 31-32S-34W
Seward County, Kansas

Surface Casing: Drilled 1715' of 12 1/4" hole. Ran 42 jts. of 8-5/8", 23# new Surface Casing, 1715' OA, set @1714'. Cemented w/700 sks Hall. Light C, 1/4# Flocele, 2%CC; 150 sks. Com. H, 3%CC. Cemented through 1" w/200 sks. Hall. Light C, 1/4# Flocele, 2%CC. Plug down @12:00 PM 8/25/80

Commenced: August 23, 1980
Completed: Sept. 8, 1980

Total Depth: 6243'

FORMATION	FROM	TO	REMARKS
Sand	0'	281'	
Sand, Red Bed	281'	600'	
Red Bed	600'	1070'	
Sand, Glorietta	1070'	1383'	
Anhydrite, Red Bed	1383'	1715'	
Anhydrite	1715'	1893'	
Shale, Lime	1893'	2105'	
Lime, Shale	2105'	2445'	
Lime	2445'	2942'	
Shale, Lime	2942'	3620'	
Shale	3620'	4150'	
Lime, Shale	4150'	4730'	
Lime	4730'	5348'	
Shale, Lime	5348'	5849'	
Lime, Shale	5849'	6243'	Logged hole
RTD		6243'	P & A

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1980
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

NRG Drilling, Inc.

By R. J. Patrick
R. J. Patrick, President

Subscribed and sworn to before me this 11th day of September 19 80

A. J. Parnell
Notary Public

My commission expires

