

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-119-20195-00-00  
API NUMBER Spud 2-5-75

RECEIVED  
JAN 16 2003  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

LEASE NAME Sanders Ranch

WELL NUMBER 2-23

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 23 TWP. 32S RGE. 29W (E) or (W)

COUNTY Meade

Date Well Completed

Plugging Commenced 1-6-03

Plugging Completed 1-9-03

LEASE OPERATOR INDIAN OIL COMPANY, INC.

ADDRESS P.O. Box 209 Medicine Lodge, Ks. 67104

PHONE (620) 886-3763 OPERATORS LICENSE NO. 31938

Character of Well Oil & Gas

Oil, Gas, O&A, SWD, (Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

Steve Durrant (KCC District Agent's Name).

Is ACC-1 filled? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 5735'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1446'	None
				5-1/2"	5709'	2560'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each sack. Plugged off bottom with sand to 4650' and 5 sacks cement. Shot pipe @4010', 3220', 2820' and 2560'. Pulled up to 1470', pumped 10 sacks gel and 50 sacks cement, pulled up to 600', pumped 25 sacks cement, pulled up to 40' and circulated 50 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Indian Oil Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 15th day of January, 2003

*Irene Herzberg*  
Notary Public

My Commission Expires:



OR