

15-129-10082-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

MORTON County. Sec. 1 Twp. 32S Rge. 42 ~~EXE~~ (W)

Location as "NE/CNW%SW%" or footage from lines C NW/4

Lease Owner Graham-Michaelis Drilling Co.

Lease Name BAUGHMAN Well No. 1

Office Address 211 North Broadway, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Low Production

Date well completed 6-28-57 19

Application for plugging filed 6-9-57 19

Application for plugging approved 6-10-57 19


Plugging commenced 6-10-57 19

Plugging completed 6-13-57 19

Reason for abandonment of well or producing formation Low Production

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3300 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Shale, Shells W/Red Bed, Sand, Anhy.</u>		<u>0</u>	<u>635*</u>	<u>8 5/8"</u>	<u>635*</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock to 2810\*, dumped 5 sacks cement. Top of cement 2785\*. Pumped in 15 sacks Gel-Mud @850\* by Sun Cementing Co.

Filled hole W/mud to 625\*, dumped 20 sacks cement. Top of cement, 570\*.

Filled hole W/mud to 35\*, set rock bridge, dumped 10 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor Graham-Michaelis Drilling Co.

Address 211 North Broadway, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

KARL DALKE (employee of owner) or (~~owner of property~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaelis Drilling Co.

(Signature) Karl Dalke

211 N. Broadway, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of June, 19 57

T. J. Grier

My commission expires 1/7/61

Notary Public.  
**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 11 1957

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 1 T. 32 R. 42W  
BOOK PAGE 16 LINE 9

BAUGHMAN #1

Well Record:

Location: C NW/4 Section 1-32S-42W Morton County, Kansas  
 Commenced: January 15, 1957  
 Completed: January 25, 1957  
 (rotary)

Operator: Graham-Michaelis Drilling Co.  
 211 North Broadway  
 Wichita, Kansas

Contractor: Graham-Michaelis Drilling Co.  
 211 North Broadway  
 Wichita, Kansas

Casing Record: 8 5/8" @ 635' W/300 sacks Common Cement  
 5 1/2" @ 3277' W/100 sacks Common Cement

LOG

Shale & Shells W/Red Bed & Sand	395
Sand, Anhy & Red Bed	920
Red Bed	1050
Anhy.	1085
Shale & Sand	1260
Sand & Red Bed	1470
Anhy. Streaks & Red Bed	1700
Anhy. Red Bed & Sand	1825
Anhy. Red Bed & Shale & Lime	2094
Red Bed - Shale & Lime	2264
Lime & Shale & Anhy.	2376
Lime & Shale	2503
Red Bed & Lime	2591
Red Bed, Lime & Shale	2648
Lime & Shale & Red Bed	2730
Lime & Shale	2795
Red Bed, Shale & Lime	2944
Lime & Shale	3172
Lime & Shale W/Red Bed	3300, RTD.

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK)

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING CO.

By John L. James  
 John L. James, Geologist.

Subscribed and sworn to before me  
 this 28th day of January, 1957.

V. D. Grier  
 V. D. Grier, Notary Public  
 My commission expires: January 7, 1961.

RECEIVED  
 STATE CORPORATION COMMISSION

PLUGGING  
 FILE SEC L T 32 R 42W  
 BOOK PAGE 16 LINE 9

JUL 11 1957  
 CONSERVATION DIVISION  
 Wichita, Kansas