

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-12920989-0000

LEASE NAME BAUGHMAN

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

LEASE OPERATOR MIDWESTERN EXPLORATION COMPANY

SEC. 1 TWP. 32 SRGE. 42W (E) or (W)

ADDRESS P.O. BOX 1884 LIBERAL, KANSAS 67901-1884

COUNTY MORTON

PHONE#(316) 624-3534 OPERATORS LICENSE NO. 5263

Date Well Completed 11-22-89

Character of Well GAS

Plugging Commenced 11-21-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-22-89

The plugging proposal was approved on NOVEMBER 17, 1989 (date)

by MR. MIKE SPAIN (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom 1/2 T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Spent In	Pulled out
None				STATE CORPORATION COMMISSION 8 5/8 DEC-6-1989	1501 2436

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
11-21-89 Pumped 25sx class H cement between rubber plugs, displaced from 2900'-3180' with 46bbls 9.5# 40 vis. mud. Pumped down casing followed & tagged by wireline. 11-22-89 Pumped 50sx class H cement via casing circulation method from 1530'-1430' displaced with 22bbls mud. Pumped 40sx class H cement, same method, 750'-650' with 10bbls mud. Pumped 10sx cement from 40' to surface same method. If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor JERRY DUNKIN, INC. License No. 8733

Address P.O. BOX 389 ENID, OKLAHOMA 73702

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Midwestern Exploration Co.

STATE OF Kansas COUNTY OF Seward, ss.

_____, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Mary Morgan

(Address) P.O. Box 1884 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 4th day of December, 19 89

Mary Morgan
Notary Public

My Commission Expires: August 3, 1992