

15-119-00130-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

MEADE County, Sec. 17 Twp. 32S Rge. 29W (E) (W)

Location as "NE/CNWxSWx" or footage from lines G SW NE

Lease Owner APACHE CORPORATION

Lease Name ANGELL Well No. 1

Office Address 823 S. DETROIT, TULSA, OKLAHOMA

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed NOVEMBER 12, 1961

Application for plugging filed NOVEMBER 13, 1961

Application for plugging approved NOVEMBER 13, 1961


Plugging commenced NOVEMBER 13, 1961

Plugging completed NOVEMBER 13, 1961

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. LACKAMP, R.R. #1, STAFFORD, KANSAS.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5808 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>SURF. SOIL, CLAY, SAND, SHALE, RED BED, LIME, SHELLS & ANHYDRITE</u>	<u>SURFACE CASING</u>	<u>-0-</u>	<u>1644'</u>	<u>8-5/8"</u>	<u>1644'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED: FILLED HOLE WITH HEAVY MUD 5808' UP TO 600'.
BRIDGED USING 1/3 SK. HULLS, HALLIBURTON
PLUG, 20 SX. CEMENT THROUGH DRILL PIPE. MUD
UP TO 35' WITH 1/2 SK. HULLS, HALLIBURTON
PLUG, 10 SX. CEMENT TO CELLAR ZERO.

JOB COMPLETED: 2:30 P.M. 11-13-61.

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1961
CONSERVATION DIVISION
Wichita

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.
Address 208 PETROLEUM BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. HONAKER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRIG. SUPT.
BOX 232, RUSSELL, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 15TH day of NOVEMBER, 1961

My commission expires 10-17-63

Leroy Duff
Notary Public.

APACHE OIL CORPORATION - Operator

SIERRA PETROLEUM CO., INC - Contractor

ANGELL #1
C SW NE
Sec. 17-32S-29W
Meade County, Kansas

T. D.: 5808'

Commenced: 10-20-61
Completed: 11-12-61

Casing:
8-5/8" Set at 1644'

Cement:
with 700 sq. cement

FORMATION	DEPTH
Surface Soil & Clay	45
Sand	380
Shale & Sand	550
Red Bed & Sand	925
Red Bed, Sand & Gravel	1345
Red Bed & Gravel	1484
Red Bed & Lime Shells	1560
Red Bed & Shale	1638
Anhydrite	1650
Red Bed & Shale	1885
Red Bed, Anhydrite & Lime	2200
Red Bed, Shale & Salt	2400
Shale, Lime & Shells	2585
Shale & Lime	2900
Lime	3148
Lime & Pyrite	3220
Lime	4303
Shale	4371
Lime w/ Shale Streaks	4442
Lime & Shale	4562
Lime	5040
Lime & Shale	5133
Lime	5150
Lime & Shale	5264
Lime	5385
Lime & Shale	5435
Lime	5808

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1961

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true
and correct to the best of my knowledge.

C.T. Honaker

Subscribed and sworn to before me this 15th day of November,
1961.

Seraphia
Notary Public

My commission expires: 10-17-63

