

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
130 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-119-20968 - 0000

LEASE NAME PEARSON "B"

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 18 TWP. 32 RGE. 29 ( X ) or (W)

COUNTY MEADE

Date Well Completed 9-26-96

Plugging Commenced 1-19-97

Plugging Completed 1-22-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-18-97 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES (12/96) If not, is well log attached? ATTACHED

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size  | Put In | Pulled Out |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8-5/8 | 1628   | NONE       |
|           |         |      |    | 5-1/2 | 5300   | 3135'      |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
MIRU PLUGGERS, PMPD 2 SX HULLS & 25 SX CMT FROM 5131-4932', SHOT OFF 5-1/2" CSG @ 3135', TOH W/5-1/2" CSG TO 3100', & SPOT 30 SX FROM 3000-3100', TOH TO 1678' & SPOT 50 SX PLUG FROM 1578-1678', TOH TO 650' & SPOT 40 SX FROM 550-650', TOH TO 40' & SPOT 10 SX PLUG FROM 40' TO 0', (HEAVY DRILLING MUD PUMPED BETWEEN EACH PLUG), CUT OFF & CAP 8-5/8 CSG 4' BELOW GL. PERMANENTLY INSCRIBE WELL NAME, LEGAL LOCATION AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGING, INC. License No. 31151  
Address P O BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) DAVID W. KAPPLE  
P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 97

My Commission Expires 5-15-99

