

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-20668-0000

LEASE NAME Fitzgerald C

WELL NUMBER 1

3300 Ft. from S Section Line

510 Ft. from E Section Line

SEC. 10 TWP. 32S RGE. 34 ~~XXX~~ (W)

COUNTY Seward

Date Well Completed 4/21/83

Plugging Commenced 2/4/87

Plugging Completed 2/13/87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Morrow Depth to Top 5429 Bottom 5434 T.D. 5750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Morrow</u>	<u>gas</u>	<u>5429</u>	<u>5439</u>	<u>8-5/8"</u>	<u>1737</u>	
				<u>5-1/2"</u>	<u>5748</u>	<u>69 its.</u>
				<u>DV tool at 4767.</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

POOH and LD 2-3/8" tubing and Retrieval D packer. RIH w/5.5" Gearhart CIBP on wireline to 5410' KB. Set CTBP. RIH w/dump bailer and dumped 2 sx cmt on top of plug. Cut off csg at 2623'. Set following Cl. H cmt plugs: 2623-2545 w/25 sx; 1776-1650 w/50 sx; 819-745' w/25 sx 40' - surf. w/10 sx. Cut off csg head 6' below Gl. welded plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DACO, Inc. License No. _____

Address Drawer 3010, Borger, TX

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver

(Address) 3545 NW 58th Street
 Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 4 day of March 1987

Deessa J. Powell
 Notary Public

My Commission Expires: 4/24/89