

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Meade SEC. 22 TWP. 32S RGE. 29W E/W
Location as in quarters or footage from lines:
C of SE NE

Locate Well
correctly on above
Section Platt.

Lease Owner IMPERIAL OIL COMPANY
Lease Name Golliker Well No. 1-22
Office Address 720 Fourth Financial Center Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 9-11-81
Plugging completed 9-16-81
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation _____ Depth to top _____ bottom _____ T.D. 5753'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1462'	none
				5-1/2"	5733'	2727'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in on location, , squeezed 5 1/2" casing with 1 sack hulls, and 50 sacks cement. Pumped
plug to 5200'. Pulled 27" tension, shot pipe @4515', 4030', 3535', 3040', 2910', 2810'
and 2715'. Pulled a total of 86 joints of pipe. Plugged well with 5 sacks hulls, 10
sacks gel, 50 sacks cement, 10 sacks gel, 8-5/8" plug, 50 sacks cement, 10 sacks gel
and 10 sacks cement. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1981

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of September, 1981

My Commission expires:



Irene Hoover
Notary Public.