

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

BELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20872-00-00

LEASE NAME Turner

RECEIVED  
MAY 03 2004

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 3

4950 Ft. from S Section Line

4850 Ft. from E Section Line

KCC WICHITA  
LEASE OPERATOR Norstar Petroleum Inc

SEC. 17 TWP. 33 RGE. 43 (SA or  W)

ADDRESS 5 Inverness Drive E. Suite 120 Englewood CO

COUNTY Morton

PHONE (303) 925 0696 OPERATORS LICENSE NO. 31652

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 9-21-01

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Plugging Completed 9-24-01

The plugging proposal was approved on 9-20-01 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACC-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Depth to Top 4712 Bottom 4720 T.D. 4860

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation     | Content            | From        | To          | Size         | Put in      | Pulled out  |
|---------------|--------------------|-------------|-------------|--------------|-------------|-------------|
| <u>Morrow</u> | <u>OIL + WATER</u> | <u>4712</u> | <u>4750</u> | <u>8 5/8</u> | <u>1418</u> | <u>-</u>    |
|               |                    |             |             | <u>4 1/2</u> | <u>4852</u> | <u>2830</u> |
|               |                    |             |             |              |             |             |
|               |                    |             |             |              |             |             |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.  
Put 60 bbls mud down 4 1/2. E.L.I set CIBP + 2.5x cmt. 4700 to 4680  
Recovered 2830 4 1/2. Pull to 1440. Circ. hole w/mud 50 sx cmt.  
1440 to 1290 40 SX 750 to 630 10 SX 40 to 0 Cut off &  
capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: NORSTAR PETROLEUM INC

STATE OF COLORADO COUNTY OF ADAIR, ss.

TER BURCHARDT (Employee of Operator) or (Operator).  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) \_\_\_\_\_



Subscribed and sworn to before me this 2<sup>ND</sup> day of Nov, 2001  
Clark D. Parrott  
Notary Public

My Commission Expires: 4-5-03