

15-129-00122-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Morton

County. Sec. 18 Twp. 33 Rge. 43W (E) (W)

Location as "NE/CNW/SW" or footage from lines 330' N & 330' E of Center Sec.
Lease Owner Terminal Facilities, Inc.

Lease Name Ball "B" #1 Well No.

Office Address Bartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-15-1953 19

Application for plugging filed 7-9-1953 19

Application for plugging approved 7-13-1953 19

Plugging commenced 8-21-1953 19

Plugging completed 8-26-1953 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R.J. Phillipe

Producing formation Depth to top Bottom Total Depth of Well 3405' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Water	3276	3258	8-5/8"	440	None
	Water	3156	3076	5 1/2"	3404	1028
	Water	3082	3074			
	Water	3032	2977			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug to 2476'; Squeezed with 100 sacks of common cement to 2000#; Reclaimed 1028' of 5 1/2" casing; Heavy Rotary mud to 26' of surface; cement to 4' of surface at which point the casing was cut off and a steel cap was welded on.

RECEIVED
STATE CORPORATION COMMISSION
SEP - 1 1953
CONSERVATION DIVISION
Wichita, Kansas

9-1-53

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Daco Lease and Well Servicing Company
Address Borger Texas

STATE OF Kansas, COUNTY OF Seward, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) R.V. Anderson

Box 70, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 19 53

My commission expires 5-23-1957

Notary Public.

PLUGGING
FILE SEC 18 T 33 R 43W
BOOK PAGE 114 LINE 1

24-2675-5 2-52-20M