

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20839-0000

LEASE NAME Bookstore A

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

4822 Ft. from S Section Line

474 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 18 TWP. 33SRGE. 43 (X) or (W)

ADDRESS P. O. Box 26100

COUNTY Morton

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 2/27/87

Character of Well Gas

Plugging Commenced 11/9/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/9/93

The plugging proposal was approved on 9/20/93 (date)

by Glen Barlow (KCC District Agent's name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Topeka Depth to Top 2717 Bottom 3292 T.D. 4700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Topeka</u>	<u>Gas</u>	<u>2717</u>	<u>3292</u>	<u>8 5/8</u>	<u>1391</u>	
				<u>5 1/2</u>	<u>5129</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set CIBP @2625' Spotted 4 sx on top of plug, RIH w/tbg, spotted 20 sx 1433'-1262', 15 sx 686'-556 & 10 sx 60' -0', Cut off & capped csq 4' below GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gibson Well Service License No. RECEIVED

Address P.O. Box 466, 713 S. Simpson, Ulysses, Ks 67880 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc. DEC 06 1993

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) Zr (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Ledlow

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 93

Jerry L Padilla
Notary Public

My Commission Expires: 8-21-96