

API NUMBER 15-129-20 783-0000

LEASE NAME Hart A

WELL NUMBER 3

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 22 TWP. 33S RGE. 43W (S.W. 1/4)

COUNTY Morton

Date Well Completed 1-31-1986

Plugging Commenced 12-8-89

Plugging Completed 12-12-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy U S A Inc.

ADDRESS Drawer K Elkhart, Kansas 67950

PHONE/ (916) 697-4427 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 Glenn Barlow

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Morrow Depth to Top 4607 Bottom 4616 T.D. 5100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Gas	4607	4616	8 5/8	1352	0
				5 1/2	5099	2814

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP W/2 sks. of cement from 4570 to 4552
Pump 50 sks. of cement from 2800 to 2700
Pump 50 sks. of cement from 1400 to 1300 Pump 30 sks. of cement from 750 to 650
Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P.O. Box 26100, OKC, OK 73126-0100

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1990

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 90

Nancy C. Huen
Notary Public

My Commission Expires: 8-8-91