

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 30 S. Market, Room 2078
 Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-129-21556-0000

LEASE NAME Bradshaw A

WELL NUMBER 2

4290 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 21 TWP. 33 RGE. 43 (E) or (W)

COUNTY Morton

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS Box 2528 Liberal, KS 67905-2528

PHONE(S) (316) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/28/98 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation none Depth to Top n/a Bottom n/a T.D. 5300'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Red bed	257	-	8-5/8 24#	1409	none
Cimarron anhydrite	anhydrite	1399	1419			
See attached drillers log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from feet to feet each set:
RIH w/OEDP to 1448'. Spotted plug #1 from 1448'-1177' w/50 sx 60/40/6 Class "H" pozmix. Pulled up to 431'. Spotted plug #2 from 431'-214' w/40 sx 60/40/6 Class "H" pozmix. Spotted surface plug from 40' to surface w/10 sx 60/40 pozmix. Plugged rat & mouse hole w/15 & 10 sx 60/40 pozmix respectively.

Name of Plugging Contractor Cheyenne Drilling License No. 5382

Address 3726 West Jones Ave Garden City, KS 67846

Name of Party Responsible for Plugging Fees: OXY USA Inc. Box 2528 Liberal, KS 67905-2528

State of Kansas County of Seward, ss.

Cal M. Wylie (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) Cal M. Wylie

(Address) Box 2528 Liberal, KS 67905-2528

SUBSCRIBED AND SWORN TO before me this 2nd day of June, 19 98

Aleta J. Arnold
 Notary Public

My Commission Expires: 2/14/99



15-129-215560000

DRILLERS LOG

OXY USA, INC.
BRADSHAW A-2
SECTION 21-T33S-R43W
MORTON COUNTY, KANSAS

COMMENCED: 04-21-98
COMPLETED: 04-29-98

SURFACE CASING: 1409' OF 8 5/8" CMTD
W/285 SKS MIDCON PREMIUM PLUS + 3% CC
+ 1/2#/SK FLOCELE. TAILED IN W/100 SKS
PREMIUM PLUS + 2% CC + 1/4 #/SK FLOCELE

FORMATION

DEPTH

SURFACE HOLE	0 - 1420
SHALE	1420 - 3020
TOPEKA	3020 - 3275
SHALE	3275 - 3490
HEBNER	3490 - 3915
HEBNER & KANSAS CITY	3915 - 4100
KANSAS CITY	4100 - 4250
MORROW	4250 - 5085
ST. LOUIS	5085 - 5215
SHALE & LIMESTONE	5215 - 5300 RTD

RECEIVED
EQUIN PA 3 1998
DIVISION
KANSAS

I DO HEREBY CERTIFY THAT THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CHEYENNE DRILLING, INC.

Wray Valentine

WRAY VALENTINE

STATE OF KANSAS : ss:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 30TH DAY OF APRIL, 1998.

JOLENE K. RUSSELL

Jolene K. Russell
NOTARY PUBLIC

JOLENE K. RUSSELL
Notary Public - State of Kansas
My Appt. Expires 9-13-99