

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

		X	

Locate well correctly on above
Section Plat

Morton County, Sec. 27 Twp. 33S Rge. 43 (E) X (W)
 Location as "NE/CNW/SW" or footage from lines 330' S & 330' E of C
 Lease Owner Cities Service Oil Company
 Lease Name Fletcher C Well No. 1
 Office Address Box 1228, Guymon, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Gas
 Date well completed 5-11 19 53
 Application for plugging filed 12-8 19 69
 Application for plugging approved 12-9 19 69
 Plugging commenced 12-15 19 69
 Plugging completed 12-30 19 69
 Reason for abandonment of well or producing formation Uneconomical to produce

If a producing well is abandoned, date of last production 4-9 19 69
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves, Box "F", Sublette, Kansas
 Producing formation Topeka Depth to top 2926 Bottom 3276 Total Depth of Well 3425 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Topeka	Gas	2926	3276	8 5/8	600	None
				5 1/2	3424	1090

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement plugs were spotted as follows: spotted 20 sx. cement from 2887' to 2727', mud from 2727' to 700'. Spotted 50 sx. common cement from 700' to 550'. Mud from 550' to 35'. Spotted 10 sx. common cement from 35' to 4' at which point the 8 5/8" casing was cut off and steel cap welded on with date and well name on cap.

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Well Service
 Address 1700 S. Main, Borger, Texas

STATE OF OKLAHOMA, COUNTY OF TEXAS, ss.
H. E. Massey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. E. Massey
Dist. Manager, Box 1228, Guymon, Oklahoma 73942
 (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1970

My commission expires 7-9-73

Melvin E. Dudley
 Melvin E. Dudley Notary Public.

RECEIVED
STATE CORPORATION COMMISSIONDEC 9 1969
CONSERVATION DIVISION
Wichita, KansasDriller's Log
Fletcher "C" #1
Sec. 27-33S-43W
Morton Co., Kansas

Clay	0 - 100
Sand & Clay	100 - 340
Red Bed	340 - 470
Red Bed & Shells	470 - 605
Shale & Shells	605 - 1195
Shale, Shells & Anhydrite	1195 - 1469
Anhydrite & Shale	1469 - 1559
Shale & Shells	1559 - 2180
Shale & Lime	2180 - 3365
Lime	3365 - 3425
T.D.	3425