

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman LLC

ADDRESS 3200 First Place Tower Tulsa OK 74103

PHONE (918) 583 3333 OPERATORS LICENSE NO. 32638

Character of Well COAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-18-00 (date)

by Hilton Hixon (KCC District Agent's Name)

Is ACO-1 filed? NO If not, is well log attached? yes

Producing Formation Tropaka Depth to Top 2831' Bottom 3029' T.O. 3192'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD STATE CORPORATION COMMISSION

RECEIVED
JAN 6 2001
CONSERVATION DIVISION
Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	624	
				5 1/2	3192	665

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each so
Rosel dumped 2 sx cmt on CIBP @ 2782. Recov. 665 5 1/2 attempt to
circ hole w/mud 50 SX 460 to 510 Tag plug @ 487 10 SX 46 to 0
cut off to capped 8 3/4 3 ft below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman, L.L.C.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

James R. Piland (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed in
the same are true and correct, so help me God.

(Signature) James Riland

(Address) 3200 First Place Tower, Tulsa, OK 74103



SWORN TO before me this 11th day of January, 2001

Kathy Garrow
Notary Public

My Commission Expires: 8-1-03

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2080

DAILY REPORT

DATE 12-15-00 FROM 100 TO 500

COMPANY

FARM NO.

Nadel and Gussman Council 1-35

HOURS WORKED

NAME

<u>4</u>	<u>D. Horton</u>
<u>4</u>	<u>J. Schoolcraft</u>
<u>4</u>	<u>A. Pineda</u>

CONTRACTOR'S TIME _____ COMPANY'S TIME 4

REMARKS: Rig up pole. Backhoe dug cellar & pit. Split casing head off 5 1/2.

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 2001

CONSERVATION DIVISION
Wichita, Kansas

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2081

DAILY REPORT

DATE 12-18-00 FROM 7⁰⁰ TO 5⁰⁰

COMPANY

FARM NO.

Nand G

Council 1-35

HOURS WORKED

NAME

10

D.H.

10

J.S.

10

A.P.

CONTRACTOR'S TIME 2 COMPANY'S TIME 8

REMARKS: Rosel dumped 2 sx cmt on CIBP
from 2782 to 2762. Rig up jacks.
Shot 5½ @ 800 & worked pipe. Shot
again @ 665 where it came loose.
Circ hole w/mud (did not circ). Mixed
50 sx plug from 660 to 500. Pull
5½ 21 jts. in all.

**SARGENT AND HORTON
PLUGGING, INC.**

Route 1, Box 49BA
Tyrone, OK 73951-9731

No. 2082

DAILY REPORT

DATE 12-19-00 FROM 7:00 TO 1:00

COMPANY

FARM NO.

N and G

Council 1-35

HOURS WORKED

NAME

6

D.H.

6

J.S.

6

A.P.

CONTRACTOR'S TIME

COMPANY'S TIME 6

REMARKS: Load out jacks. Wait on KCC.
Tagged plug @ 487. Load hole w/
mud to 40. Mixed 10 sx 40 to O.
Cut off & capped 8 5/8 3 ft. below
G.L. Tore down to tally pipe. 21
jts. in all.