

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 6 TWP. 34 RGE. 11w E/W
Location as in quarters or footage from lines:
NE NE NW

Locate Well
correctly on above
Section Platt.

Lease Owner Kaiser-Francis Oil Company
Lease Name Grodercke E #1 Well No. _____
Office Address Box 791, Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2/26/83
Plugging completed 3/3/83
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation _____ Depth to top _____ bottom T.D. 4686'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	230'	none
				5 1/2"	4686'	3283'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped bottom with 35 sacks cement & 5 1/2" plug to 4500'. Shot casing at
3700' & 3509' & 3309'. Pulled total of 101 joints. Plugged well with
3 hulls, 20 gel, 70 sacks 50/50 pos 4% gel 3% c.c., 15 sacks gel, 1 sack
hulls, plug, & 100 sacks 50/50 pos. 4% gel 3% c.c.


Plugging complete

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1983

My Commission expires: 

[Signature]
RECEIVED Notary Public.
STATE CORPORATION COMMISSION

MAR 14 1983
CONSERVATION DIVISION
Wichita, Kansas

15-007-01294-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Francis Oil & Gas, Inc.


SEC. 6 T. 34 R. 11W
LOC. NE1/4

FARM Groendycke NO. E 1

TOTAL DEPTH 4685
COMM. 11/6/57 COMP. 11/22/57
SHOT OR TREATED
CONTRACTOR ARMOR, Inc.
ISSUED

COUNTY Barber

KANSAS



CASING
20 10
15 8 231'
12 6
13 5 4684'

ELEVATION 1148 K.F.
1146 N.F.
1144 O.F.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Topsoil & Red Bed	130
Red Bed & Shells	231
Red Bed & Shale	680
Shale & Shells	1635
Lime & Shale	1755
Lime, Shale & Sand	1845
Lime & Shale	2040
Lime	2140
Lime & Shale	2535
Shale	2710
Shale & Lime	3190
Shale & Sandy Lime	3310
Lime & Shale	4060
Lime	4165
Lime & Shale	4221
Lime	4380
Shale & Lime	4485
Lime	4505
Shale & Lime	4590
Lime	4620
Cherty Lime	4630
Chert & Lime	4650
Cherty Lime	4685

FORMATION TOPS:
Brown Lime 3873
White Lime 3881
Mississippi 4572

FILE COPY
RECEIVED
STATE OPERATIONAL COMMISSION
DEC 2 1962
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMOR, INC.

By L. C. Sporenberg
L. C. Sporenberg

STATE OF KANSAS)
) SS
COUNTY OF SEDWICK)

Subscribed and sworn to before me, a notary public, in and for said county and state this 27th day of November 1957.

My commission expires February 13, 1960.

Robert F. Furey