

15-007-00114-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 6 Twp. 34S Rge. 11 (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW NW/4
Lease Owner Gulf Oil Corporation
Lease Name Groendycke Well No. 1
Office Address Box 661, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-15 1955
Application for plugging filed 5-16 1955
Application for plugging approved 5-16 1955
Plugging commenced 5-16 1955
Plugging completed 5-16 1955
Reason for abandonment of well or producing formation Dry Hole

NORTH

X			

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5275 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	256'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 260' of surface, set wood plug with 1/3 sack hulls, and ran 20 sacks cement. Mudded to 30' of surface, set wood plug with 1/3 sack hulls, and capped with 10 sacks cement filling hole into cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Company
Address 1612 First National Bank Building, Tulsa 3, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.
W. H. Duley (employee of owner) or (Contractor) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley
Box 544, Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1955

My commission expires April 14, 1956

Sam Cornell Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1955

5-17-55

PLUGGING CONSERVATION DIVISION
FILE SEC 6 T 34 S 11 W
BOOK PAGE 119 LINE 33

Wichita, Kansas

15-007-00114-0000

WELL RECORD
GULF T 280-A PRINTED IN U.S.A.

WELL NO. **1** LEASE **Greenfield** COMPANY **Gulf Oil Corporation** A.F.E. **6912 (12-1)**
 DATE-DRILLING BEGAN **4-16-55** WELL COMPLETED **5-16-55** FIRST PRODUCTION **Dry**
 SAND RECORD **Dry Hole - Plugged and Abandoned** TOTAL DEPTH **5275**

INITIAL PRODUCTION

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	BACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
10-3/4	*	*	A	*	265	275			265
* 1 jts. 337, BR, OS 4 jts. 297, IR, SI									

S-6 T-3LS R-11H

0					

Distance H - 9' from RHD to top 10-3/4" casing.

ELEVATION **1196'**

FORMATION RECORD

Formation	From	To
Red bed	0	265
Shale & shells		940
Red bed		1060
Shale & shells		1710
Shale & lime streaks		1905
Lime & shale		2090
Shale & lime		2190
Lime		2320
Shale & lime		2830
Lime & shale		2930
Shale & lime		3065
Lime		3230
Lime & shale		3675
Lime, sand & shale		3740
Shale & sand		3905
Lime		4245
Lime & shale		4215
Lime		4255
Lime & shale		4310
Lime		4380
Lime & marl		4430
Lime		4591
Lime & shale		4637
Lime		4698-1/2
Charly lime		4705
Mississippi lime		4722
Lime & shale		4746
Lime		4805
Lime & shale		4850
Lime		4855
Shale (Kinderhook)		4915
Shale		4971
Shale & lime		4985
Lime		5114
Sand & shale		5169
Shale & sand		5200
Shale & lime		5232
Sand & shale		5253
Shale & lime		5260
Lime		5275
Total Depth		5275

PLUGGING
 FILE SEC 6 T 34 R 11W
 BOOK PAGE 119 LINE 33

RECEIVED
 STATE CORPORATION
 JUN 3 1955
 CONSERVATION DIVISION
 Wichita, Kansas