


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 6 Twp. 34S Rge. 11 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
100' E of C NW SE

Lease Owner Kansas Oil Corporation
Lease Name Bevans Well No. 1
Office Address 400 N. Woodlawn, Suite 20, Wichita, Ks., 67208
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Jan. 28, 1978
Application for plugging filed (verbally) Jan 28, 1978
Application for plugging approved (verbally) Jan 28, 1978
Plugging commenced Jan 28, 1978
Plugging completed Jan 28, 1978

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Owens
Producing formation Depth to top Bottom Total Depth of Well 4690
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	CONSERVATION DIVISION Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Set 1st plug at 300' with 30 sacks
2nd plug at 40'- solid bridge - with 12 sacks
3 sacks in rat hole
Plug was down at 11:30 a.m., January 28, 1978


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Ass't. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 1978
My commission expires July 21, 1979
Sandra Richman Notary Public



CONTRACTOR'S WELL LOG

OPERATOR: Kansas Oil Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Bevans #1
 LOCATION: 100' E of C NW SE Section 6-34S-11W
 Barber County, Kansas
 SPUD DATE: January 18, 1978
 COMPLETION DATE: January 28, 1978

0	295	Clay & shale
295	945	Red bed & shale
945	1350	Shale
1350	1368	Anhydrite
1368	1617	Shale & lime
1617	2007	Lime & shale
2007	2075	Shale & lime
2075	2535	Lime & shale
2535	2788	Shale & lime
2788	3218	Lime & shale
3218	3420	Shale & lime
3420	3810	Lime & shale
3810	3995	Shale & lime
3995	4165	Lime & shale
4165	4572	Lime
4572	4624	Shale & lime
4624	4690	Lime
	4690	Rotary Total Depth

Spud hole at 5:30 p.m., January 18, 1978. Drilled 300' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 28# surface casing. Set at 294' K.B. Cemented with 175 sacks common cement, 3% CaCl, 2% gel. Cement did circulate. Plug was down at 11:30 p.m., January 18, 1978.

T.D. 4690'. Set 1st plug at 300' with 30 sacks, 2nd plug at 40' - solid bridge - with 12 sacks, 3 sacks in rat hole. Plug was down at 11:30 a.m., January 28, 1978.

SAMPLE TOPS:
 Anhydrite 1349 (+113)
 B/Anhydrite 1368 (+ 94)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 07 1978

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Bevans #1, 100' E of C NW SE Section 6-34S-11W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge, Ass't. Sec.-Treas.



Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state on this 2nd day of February, 1978.

My commission expires July 21, 1979.

Sandra Richman
 Sandra Richman, Notary Public