


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County, Sec. 18 Twp. 30 Rge. 6 (E) (W)
Location as "NE/CNW/SW" or footage from lines C N/2 NE
Lease Owner Rains & Williamson Oil Co.
Lease Name Messinger A#1 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7/11/73 19
Plugging completed 7/16/73 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4531 Feet
Showing depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8 5/2	310 4332	none 2184

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Allied pumped 10 sacks gel, 10 sacks cement. Shot pipe at 3108', 3011', 2913', 2815', pulled 85 joints. Bailed hole to 310' and set 10' rock bridge. Dumped 5 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1973

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet) KNIGHT CASING PULLING CO. INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 1973

My commission expires [Stamp]
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

[Signature]
Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson
Oil Co., Inc.
MESSENGER "A" #1
C N $\frac{1}{2}$ NE 18-30S-6W
Kingman County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.
Commenced: 6-24-68
Completed: 7-11-68 (Rotary)

Remarks: Set 8-5/8" surface casing at 310' with 260 sacks cement.

Set 5-1/2" casing at 4332' with 200 sacks cement.

Formations

Sand	35'
Shale and Shells	97'
Red Bed	310'
Red Bed and Shale	565'
Shale and Shells	1050'
Lime	1135'
Shale	1220'
Lime with Shale	2317'
Shale and Lime	2590'
Lime and Shale	3615'
Lime	3750'
Lime and Shale	3850'
Lime	4005'
Lime and Shale	4060'
Lime and Chert	4330'
Lime	4346'
Lime and Shale	4466'
Lime	4531'
Rotary Total Depth	4531'


RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1973
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 16th day of July, 1968.


Sherry Gish Notary Public

My Commission Expires:
6-30-71

