


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit.
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Kingman County, Sec. 16 Twp. 30 Rge. 6 (E) E (W) X
Location as "NE/CNWxSWx" or footage from lines C SW SE SW?
Lease Owner Eli Wilkonson
Lease Name Riggs Well No. 2
Office Address 415 Philtower Bldg. Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 7-31-66 19
Application for plugging filed 7-6-70 19
Application for plugging approved 7-8-70 19
Plugging commenced 7-13-70 19
Plugging completed 7-17-70 19
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G.R. Barbstine
Producing formation Depth to top Bottom Total Depth of Well 4308' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	259'	none
				5 1/2"	4307'	2890.64'

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill bottom from 4308' to 4280' with gravel, mix and dump 5 sacks cement.

Set 10' rock bridge from 240' to 230', mix and dump 4 yards ready mix to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Richard C. Housman

Sworn to before me this 30 day of July, 19 70

(Address) James Davis

My commission expires Sept. 19, 1971

Notary Public.



75-095-30096-0000

COPY

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SHAW-HUGHES

SEC. 16 T. 30 R. 6W
LOC. C SW SW

FARM Riggs No. 2

COUNTY Kingman

TOTAL DEPTH 4308'

COMM. 7-20-66

COMP. 7-31-66

SHOT OR TREATED
CONTRACTOR Garvey Drig.

ISSUED 12-10-66

CASING

20 10
15 8 5/8" 259' cem w/ 225 sx'
12 6
13 5 1/2" 4307' cem w/ 200 sx

ELEVATION 1397' KA

PRODUCTION SWDW RATE SATIS.
(Miss 4096-98 & 4104-06)

FIGURES INDICATE BOTTOM OF FORMATIONS

FIGURES INDICATE BOTTOM OF FORMATIONS

- 260' Sand and Red Bed
- 400' Red Bed and Shale
- 680' Shale
- 1290' Shale and Lime
- 1320' Anhydrite
- 1530' Shale and Lime
- 1830' Lime and Shale
- 2175' Shale
- 3000' Shale and Lime
- 3495' Lime and Shale
- 3716' Lime
- 3800' Lime and Shale
- 3890' Shale and Lime
- 4078' Lime and Shale
- 4100' Chert
- 4210' Chert and Lime
- 4308' Chert
- 4308' RTD

- TOPS: SCOUT
- Lansing 3496
- Base Kansas City 3745
- Re-Mississippi 4060
- Mississippi Chert 4078

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1970
CONSERVATION DIVISION
Wichita, Kansas

*Perf 4094-96
4101-06
Completed as SWD
pursuant to rules & order
of Kansas Corp. Commission*

State of Kansas

County of Barton

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Riggs No. 2 well.

Sam N. Stephens

Subscribed and sworn to before me this 10th day of August 1966

My Commission Expires: May 28, 1969

Richard H. Dumble
NOTARY PUBLIC