

15-119-10182-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 20 Twp. 32S Rge. 29W (E) (W)

Location as "NE/CNW/SW" or footage from lines 660' from South & West Lines SW

Lease Owner Sinclair Oil & Gas Company

Lease Name Mamie E. Angell Well No. 3

Office Address P. O. Box 466, Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-29-61 19

Application for plugging filed 3-29-61 4-1-61 19

Application for plugging approved 4-1-61 19

Plugging commenced 4-8-61 19

Plugging completed 4-10-61 19

Reason for abandonment of well or producing formation Dry hole - Non-productive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes -

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation None encountered Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>None encountered</u>				<u>8-5/8"</u>	<u>1572</u>	<u>None</u>
				<u>4 1/2"</u>	<u>5668'</u>	<u>3071'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement from TD5749 to 5635' sanded from 5635 to 5500', from 5500' to 5450, 5 sacks cement, sand from 5450 to 5430', mud from 5430 to 600', 10' rock bridge to 590', from 590' to 540' with 20 sacks cement from 540' to 40' with mud, from 40' to 30' with 10' rock bridge and from 30' to base of cellar with cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company

Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.

C. E. Most (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Most
Dist. Supt.
Box 466, Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 61

My commission expires Aug. 13, 1962

L. B. Reynolds Notary Public.

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

MAMIE E. ANGELL #3
C SW SW SECTION 20-32S-29W
MEADE COUNTY, KANSAS

COMMENCED: FEBRUARY 17, 1961

COMPLETED: MARCH 11, 1961

OPERATOR - SINCLAIR OIL & GAS COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	40	SURFACE SOIL & SAND	
40	540	SHALE, SHELLS & SAND	
540	940	RED ROCK	
940	1000	RED ROCK & SHELLS	
1000	1065	SHALE & SHELLS	
1065	1355	SAND & SHALE	
1355	1465	SHALE & LIME	
1465	1571	SHELLS	RAN 51 JOINTS OF 8-5/8" CASING, CEMENTED @ 1570' W/850 SACKS CEMENT
1571	1590	SHALE	
1590	1920	SHALE & LIME	
1920	2200	SHALE & SHELLS	
2200	2680	LIME & SHALE	
2680	2810	LIME	
2810	3035	LIME & SHALE	
3035	3248	LIME	
3248	3580	LIME & SHALE	
3580	3710	SHALE & SHELLS	
3710	3844	SHALE & LIME	
3844	3912	LIME	
3912	4105	BROKEN LIME & SHALE	
4105	4345	SHALE & SHELLS	
4345	4469	LIME & SHALE	
4469	5531	LIME	
5531	5571	LIME & SHALE	
5571	5675	LIME	
5675	5749	LIME & SHALE	
5749	TD		RAN 5649' OF 4-1/2" CASING, CEMENTED @ 5649' W/250 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1961
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE WELL DRILLED IN C SW SW SECTION 20-32S-29W, MEADE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 14TH DAY OF MARCH, 1961, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1963

Vira A. McKenzie
VIRA A. MCKENZIE, NOTARY PUBLIC