

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20741 - 000 /

LEASE NAME E. Paul Boles

WELL NUMBER 2-11

2300 Ft. from S Section Line

3180 Ft. from E Section Line

SEC. 11 TWP. 32S RGE. 34 (E) or (W)

COUNTY Seward

Date Well Completed 10-23-87

Plugging Commenced 4-21-93

Plugging Completed 4-21-93

LEASE OPERATOR UNION PACIFIC RESOURCES COMPANY

ADDRESS P.O. Box 7 - MS 3407, Ft. Worth, Texas 76101-0007

PHONE# (817) 877-6530 OPERATORS LICENSE NO. 06417

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/14/93 (date)
by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Lansing/KC Plattsburg Depth to Top 4172' Bottom 4180' T.D. 6870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	Oil	0	1631'	8-5/8"		
Marmaton		0	5663	4-1/2"		
Chester						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Set CIBP at 4775'. Dump 2 SXS cement on top set CIBP at 4125'. Dump 2 SXS cement on top fill hole with mud.
Set 25 SXS cement plug at 1650'. Set 25 SXS cement plug at 675'. Set 5 SXS of cement plug at 50'. No pipe recovered. Cut 8-5/8" csg. off 6' below GL. Weld on steel cap empty workover pit. Fill pit & cellar.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kurt Williams @ J.W. Gibson License No. 05866

Address P.O. Box 160, Ft. Morgan, CO., 80701


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: UPRC

STATE OF Texas COUNTY OF Tarrant, ss.

Cami Minzenmayer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cami Minzenmayer

(Address) P.O. Box 7 - MS 3407, Ft. Worth, TX 76101-0007



Subscribed and sworn to before me this 4 day of May, 19 93

Tracie J. Sanderson
Notary Public

MAY 10 1993

My Commission Expires: 06-12-93

CONSERVATION DIVISION
WICHITA, KS