

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20797-0000

LEASE NAME Fitzgerald "C"

WELL NUMBER 4-11

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 11 TWP. 32S RGE. 34 (E) or (W)

COUNTY Seward

Date Well Completed 1-12-85

Plugging Commenced 5-24-93

Plugging Completed 5-24-93

LEASE OPERATOR Union Pacific Resources Company

ADDRESS P.O. Box 7 MS 3407, Fort Worth, TX 76101-0007

PHONE# (817) 877-6530 OPERATORS LICENSE NO. 06417

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-24-93 (date)

by Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 4211' Bottom 4221' T.D. 5650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Heebner	Oil	0	1676'	8 5/8"		
Lansing	Oil	0	5659'	5 1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PCH with rods, pump & 2 3/8" tubing. Set CIBP @ 1150' with wireline unit. Dump 2 sxs cement on plug. Load hole with mud. Cut casing at 1650'. Could not pull RIH with tubing. Set 40 sxs cement plug at 1650'. PU hole. Set 30 sxs cement plug at 700'. PU hole & set 5 sxs surface to 40'. Pump 8 sxs. Cut off casing 4' below ground. Weld on steel cap. Remove fluid from pit. Backfill pit and cellar.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Tim Hintergardt @ J.W. Gibson License No. 05866

Address P.O. Box 160, Fort Morgan, CO 80701


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Union Pacific Resources Company

STATE OF Texas COUNTY OF Tarrant, ss.

Cami Minzenmayer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Cami Minzenmayer

(Address) P.O. Box 7 MS 3407 Fort Worth, TX 76101-0007



AND SWORN TO before me this 15th day of June, 19 93

Rachelle Montgomery
Notary Public

Commission Expires: 10-31-94