

APR 18 2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas Liberal KS 67905

PHONE # (316) 629 4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-27-2000 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation morrow Depth to Top 5357 Bottom 5366 T.D. 5798

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 3/8	1635	-
				5 1/2	5797	1729

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each:
Mixed 2 5x hulls & 25 5x cmt. to plug perf's from 5357 to 5157, Recov. 1729
5 1/2. Pulled to 1660 & circ. hole w/mud. Mixed 65 5x plug from 1660 to 1460
50 5x 550 to 400 10 5x 40 to 0 Cut off & capped 8 3/8 3 ft below G.L.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address Box 506 Liberal KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Kenny L. Andrews (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fa. statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 6528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 10th day of April, 2000

NOTARY PUBLIC, State of Kansas
ANITA PETERSON
My Appt. Exp. Oct. 1, 2001

Anita Peterson
Notary Public

My Commission Expires: Oct. 1, 2001

