

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Well was completed on:  
API NUMBER 15-175-21143 -0000

LEASE NAME Stoner A

WELL NUMBER 3

1800 Ft. from S Section Line

1700 Ft. from E Section Line

SEC. 14 TWP. 32S RGE. 34 (REV. 11)

COUNTY Seward

Date Well Completed 12-4-90

Plugging Commenced 4-30-91

Plugging Completed 4-30-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 19, 1991 (date)

by Mr. Glenn Barlow of District #1 (KCC District Agent's Name).

Well was completed on:  
Is ACO-1 filed? Yes if not, Is well log attached? Yes

Producing Formation Chase Depth to Top 2588 Bottom 2694 T.D. 3020'

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To   | Size   | Put In | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| Chase     | Gas     | 2588 | 2694 | 8 5/8" | 1705'  |            |
|           |         |      |      | 5 1/2" | 3019'  |            |

MAY 09 1991

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP at 2550'. Dumped 2 sx cmt from CIBP. Spotted 30 sx of Cl.H cmt from 1805 to 1557. Spotted 50 sx of Cl.H cmt from 800 to 385. Spotted 10 sx Cl.H cmt from 70' to surface. Cut off 8 5/8" & 5 1/2" csg 4' below GL and welded on ID. State Witness: Mr. Glenn Barlow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents' Casing Pulling Co. License No. 5671

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 91

Lay Ann Kilmer  
Notary Public

My Commission Expires: 4-11-94